
QUOTATION

TO:	FROM:
Mr. Kanak Pansari Director Bbell Industry LLP GIDC Saykha, Saykha Extension, Dist.-Bharuch (India) Mobile: +91-9819304676 E-mail: kanakjansari@gmail.com	Amresh R. Mehta Director Futura Digital Technologies Private Limited 315, Samanvay Silver, Nr. Mujmahuda Circle, Vadodara, Gujarat (INDIA)- 390020 Mobile: +919825000891 E-mail: amresh@futuraDX.com www.futuraDX.com
COMPANY:	DATE:
BELL INDUSTRY LLP (BBELL)	04 TH DEC 2023
FAX NUMBER:	TOTAL NO. OF PAGES INCLUDING COVER:
	5
PHONE NUMBER OF SENDER:	SENDER'S REFERENCE NUMBER:
+91-265-4000037	2023/1219/R1
RE:	YOUR REFERENCE NUMBER:
Scope of Work- ETP Piloting Services	Request from Mr. Kanak Pansari post conclusion of lab trials at Futura Process Labs at Vadodara & subsequent discussion

Dear Sir,

We are pleased to submit our revised offer for ETP Piloting Services with Futura Catalytic Treatment (CTB) Process Unit which would include its display of efficacy and operation for Effluent Water Treatment for the provided stream of effluent from your Saykha facility at Gujarat.

1.0 Piloting Services Objective & Effluent Stream at BBell Industry LLP (BBELL)

BBELL has an existing plant and an ETP where they generate a composite effluent from various plant mix (Tank 2 + Tank 3 + Tank 4). The current total effluent stream hydraulic load is about 35-40 KL per day. Currently they are treating the effluent using MEE and the condensate water is re-used / discharged to CETP. The client has CETP membership. The current cost of operation of MEE + ATFD is very high and the BBELL team is looking for a solution to reduce their current operating cost as well as how to avoid running the MEE + ATFD operation.

On the above effluent sample, multiple treatability studies were carried out at Futura Process Labs and very encouraging results were obtained and shared with the client. The results were presented to the client and the client would now like to carry out piloting trials as a further confidence building measure onsite premises.

After encouraging results were obtained, it was then considered to conduct similar trials on larger quantities of the effluents as a confidence building measure prior to opting for a full working scale plant. Piloting of the

Registered Address:

Futura Digital Technologies Private Limited
315, Samanvay Silver, Nr. Mujmahuda Circle, Vadodara, Gujarat (INDIA) 390020
Contact Number: +91-265-400 0037
info@futuraDX.com
www.futuraDX.com



Water
Solutions



Digital
Technologies



Cyber Security
& IT Solutions

Futura CTB Process Technology shall result in the following outcomes:

- ✓ Confidence in the technology shall be uplifted further when observing consistent desirable results in larger quantities.
- ✓ The batch cycle time and input of resources such as electricity, operating chemicals and other consumables for treatment of the effluents of BBELL can be ascertained and optimized which shall further assist Futura officials in determining the considerations required for the full-scale working plant.

The scope of this proposal is to provide piloting services with customized Futura CTB Process Treatment for targeting the effluent objective as listed in the table below

1.1 Operating Parameters for Futura Catalytic Treatment (CTB) Process for Piloting Trials

Parameter	Values as INPUT to Pilot Unit	Values as OUTPUT from Pilot Unit	UOM
Design Capacity	200 LPH	90% (approx.) with filtration	LPH
Operating pH Load	2.00 – 8.30	6.50 – 8.50	
Operating TDS Load	≤ 9,000	± 10% of Inlet	ppm
Operating COD Load	≤ 9,000	≤ 2,500	ppm
Operating TSS Load	≤ 1,000	≤ 50	ppm
Operating NH3-N Load	≤ 600	≤ 100	ppm
Color	≤ 1,000	≤ 300	ptco

2.0 Piloting Services Equipment

The below listed wastewater treatment systems and equipment shall be mobilized under this piloting services scope

- 1) Raw Effluent Collection and pH Neutralization
- 2) Coagulation & Flocculation
- 3) Chemical Dosing Skids
- 4) Catalytic Treatment using CTB Skid
- 5) Filtration System

The pilot shall be designed for BBell targeted effluents listed above with a design capacity of 200 LPH; Monday through Friday) and shall be all modular skid mounted plug & play type. All equipment shall be occupied and operated on a temporary basis for **a maximum period of 12 working days** within which trials of the above effluent shall be completed. Before beginning the actual effluent trials, we need one (1) full day to dry run and streamline the pilot plant at site for it to receive the effluent. We request BBell team to arrange and keep ready the requested setup and assistance to ensure timely setup and completion of the targeted effluent trials.

Registered Address:

Futura Digital Technologies Private Limited
 315, Samanvay Silver, Nr. Mujmahuda Circle, Vadodara, Gujarat (INDIA) 390020
 Contact Number: +91-265-400 0037
info@futuraDX.com
www.futuraDX.com

3.0 Arrangement and Assistance in the Scope of BBELL

The below listed assistance and arrangement shall be in the scope of BBELL and it's important that all the below is ready and arranged before the pilot plant is mobilized at site for effective and efficient use of time, energy and resources after the entire system, equipment and manpower is mobilized under this piloting services scope.

- **All the effluent samples planned above, are representative samples for the actual effluent that is expected to be generated during production. Hence it is important that each one is tested at client labs at least for pH, COD, NH3-N TSS, and TDS to ensure consistency with the characteristics before the same is subjected to Piloting Services.**
- Loading, unloading and shifting and positing of the piloting equipment and systems onsite from time to time from transport vessel to the allocated site and into position
- Demobilization and loading of the piloting equipment and systems on transport vehicles.
- 3-phase 415V/50Hz power connection (5 KW Load) at various panels (RYBN) with its isolation MCB.
- 1-phase 230V power connection for upto six (6) plugs for misc. connections like small dewatering pumps, portable TDS probe, portable pH probe etc
- 2000 liters utility water for general wash at the beginning of the pilot trials and similar quantity of utility water at the end of the pilot trials prior to demobilizing.
- Leveled surface and a clutter free space of about 35 feet X 20 feet for placing the pilot modules and skids
- Any nature / characteristic of hazard or flammability or explosiveness or any special handling requirements due to the compounds in the effluent MUST BE mentioned by the client prior to the treatability study.
- Responsibility of disposal of any left over untreated effluent or wash water, treated effluent, sludge/waste, Used consumables etc from the running or setting up of the pilot plant.
- All storage tanks for Raw Effluent Holding and Final Treated Effluent Holding shall be provided by client in clean and usable conditions.
- Lock and key room/storage for mechanical tool kit and any spares that may be required during the pilot trials.
- Providing 2 full time helpers throughout the trial (2 helpers) and 1 fitter as an when required during the piloting trials upon request.
- Timely arrangement of the effluent sample batches in required quantity, duly tested for it being representative in terms of **pH, COD, TSS, NH3-N and TDS** and any other parameter before providing for trial runs (all the effluent batches shall be planned and intimated)
- Any special documentation or criteria for arrangement of preparing a returnable gate pass or any BBELL requirement shall be specified before mobilization of the pilot unit at site
- Client shall arrange for drinking water, food, office area for Site Operations Team to work with their computers (3 people desk space or conference room) with internet access.

Registered Address:

Futura Digital Technologies Private Limited
315, Samanvay Silver, Nr. Mujmahuda Circle, Vadodara, Gujarat (INDIA) 390020
Contact Number: +91-265-400 0037
info@futuraDX.com
www.futuraDX.com



Water
Solutions



Digital
Technologies



Cyber Security
& IT Solutions

4.0 Cost Element

Cost Element – PILOTING SERVICE CHARGES	Amount (INR)
ETP Wastewater Stream: Piloting Services using Futura Catalytic (CTB) Treatment Including- pH Neutralization, Coagulation and Flocculation followed by Filtration Setup, Catalytic Treatment (CTB) Skid for Total 12 working days (No items are being sold)	5,30,000.00
SUB TOTAL	5,30,000.00
+ Applicable GST @ 18.00 % Payment Terms: 90% advance, 10% upon completion of Pilot Trials.	
Additional Piloting Services Man-Day Charges: For any additional trial days above <u>12 working days</u> for carrying out Piloting Services using Futura Catalytic (CTB) Treatment Including- pH Neutralization, Coagulation and Flocculation followed by Filtration Setup, Catalytic Treatment (CTB) Skid Quoted as Man-Day Charges and shall be applicable as extra over and above the piloting service charges quoted calculated on number of extra man-days.	8,500.00
+ Applicable GST @ 18.00 % Payment Terms: 100% of Total Additional Charges (computed on number of total extra days) immediately after completion of Pilot Trials and before Demobilization of Piloting Equipment.	


5.0 Terms & Conditions:

- The **pilot plant is mobilized to BBELL site for an extension of a maximum period of 3 days.** Futura will not be able to extend the piloting services beyond this period whatsoever.
- Futura Pilot Plant shall be operated only under the physical presence and / or strict supervision of Futura deployed Site Operations Team. The piloting trial equipment shall not be operated or handled or troubleshooted / opened or repaired in absence of Futura Site Operations Team. In any such acts, Futura will have the right to discontinue the pilot trials and demobilize the piloting equipment and discontinue further services.
- In situations where the site or the client team is not ready and our site team is waiting and idle for reasons not accounted to Futura, shall be considered as a working day for trial.
- All transport costs of piloting equipment to and fro from Baroda- Saykha - Baroda shall be extra at actual.
- All travel, local commute, lodging and boarding to Saykha (up to BBELL piloting site premises) shall be extra at actual or arranged by client for our site teams.

Registered Address:

Futura Digital Technologies Private Limited
315, Samanvay Silver, Nr. Mujmahuda Circle, Vadodara, Gujarat (INDIA) 390020
Contact Number: +91-265-400 0037
info@futuraDX.com
www.futuraDX.com

Sincerely,



Amresh R. Mehta
Director



**Water
Solutions**

Futura Digital Technologies Pvt. Ltd.
315, Samanvay Silver,
Nr. Mujmahuda Circle,
Vadodara, Gujarat (INDIA)
390020

CIN: U72100GJ2019PTC110630
GSTIN: 24AADCF8975D1Z1
PAN No: AADCF8975D
HSN: 998337

Phone : +91 265-400 0037
Mobile : +91 9825000891
Email : amresh@futuraDX.com
Web : www.futuraDX.com

Registered Address:

Futura Digital Technologies Private Limited
315, Samanvay Silver, Nr. Mujmahuda Circle, Vadodara, Gujarat (INDIA) 390020
Contact Number: +91-265-400 0037
info@futuraDX.com
www.futuraDX.com



Water
Solutions



Digital
Technologies



Cyber Security
& IT Solutions