



SINTEX BAPL LTD

REF: SGS/001/23-24/934.

Date: 16.08.2023

**K/A. To : BBell Industry LLP
Vagra-Bharuch**

SUB : Quotation for Modification in Factory's AST to STP 10KLD (AST Type).

Dear Sir,

Thank for your query regarding the Modification in AST (AST to STP Tank), At a time of my Physical Visit at your Plant, Pls find the Quote & Hope the same will be in line of your expectation.

Sr. No	Description	QTY	RATE	AMOUNT
1.	Repair & Maintenance	01		555675.00
2.	Sintex Man Days	05	7500.00	37500.00
	Total			593175.00
	GST @ 18%			106772.00
	Net payable Amount			<u>699947.00</u>

Rs. Six Lac ninty nine thousand nine hundred fourty seven only...

Tank Modification Work Breakup:-

BBELL Industry LLP- Dahej			TTP System	
	Factory Building AST 10KL	Qty		PSF
1	Making Aeration Chamber	1		ACF
2	Floattng Midea	10000		All Mideas for filters
3	TTP System 2m3	1		Dosing Pump
4	Recirculation Pump 1HP	1		TTP Feed Pump-02 nos,
5	4core Cable 3phase for Pump Feed Pump & Recirculation Pump	10mtr		1HP control Panel-02nos/1nos. With Level Sensor -02qty
6	Flexible hose Pipe for Pump	9mtr		CV tank for hypo Storage
7	Blower 0.3kg/cm2 with Motor 2 HP	2		Sodium Hypo- 50Ltr
8	Piping and Consumable			& Multi port valve with TTP system
9	Bact Culture	10KG		Installation with TTP Piping & Cabling
10	Nutri Sarv	3kG		
11	Control Panel for Blowers, Recirculation Pump, Feed Pumps, dosing Pump	1		
12	Tank Cleaning/Media Refelling	1		

Scope of Work (Customer):-

1. Arrange to Inlet Diversion During the Work in factory's STP Tank (Approx. 5 Days) will be in Customer scope.
2. All Civil Work will be in Customer Scope like Digging pits, New Civil storage tank etc...
3. Desludging of the Tank with Tankers will be in Customer Scope, If required to clean by Hand that will be arrange by the Sintex..
4. Three Phase Electric Line Connection lying at Installation Point where both Blower & TTP Pumps to be install will be in Customer scope.
5. Exhaust Fan, LED Light connection (Inside of the Tank) and waste Cotton Cloths will be in Customer Scope.
6. Will be made one RCC Tank/Plastic tank for Sad-link Zone (**Approx. 5KL Capacity.**)
7. Blower Room will be made by Customer for safety from Weather effect.

Scope of Work (Sintex):-

1. Aeration Pipe line will be Connect from Blower to STP Tank (Inside by the Sintex).
2. The Second chamber of existing AST tank will be convert in Aeration zone by Sintex Team.
3. Tank Cleaning after Desludging work will be in Sintex Scope.
4. Dosing Pump installation and Pipe for Dosing supply will be install by the Sintex.
5. TTP Installation (Including ACF & PSF) will be Install by Sintex team.
6. Both Blowers with 2 HP Motor will be Install by Sintex Team.
7. All Electrical & Pipe line connection from the Main line to Blower & Dosing Pump by the Sintex Only.
8. Defuser will be made by the Sintex for Proper Aeration Supply inside of the Tank.
9. Partition wall inside of the Tank will be Cut by Sintex for further Work.
10. After Repairing & Modification work additional Bacterial Culture will be dropped by the Sintex in aeration Chamber.
11. All Automation will be do by Sintex Like Blower automation, TTP Feed pump & Recirculation Pump.

Terms And Condition:

- 1) **Payment : 100% advance against the Performa Invoice by Cheque or D.D. in favor of Sintex BAPL Ltd – payable at Kalol (North Gujarat).**
- 2) **Transportation cost will be extra as applicable.**

Note: Sintex will not be responsible for any collateral losses occur due to Sintex product failure for any reason.

You are requested to approve the quotation along with Advance payment to enable us to arrange the materials and manpower at site.

Thanks and Regards,
For Sintex BAPL Ltd.