



SINTEX BAPL LTD



REF: SGS/001/23-24/933.

Date: 16.08.2023

K/A. To : **BBell Industry LLP**
Vagra-Bharuch

SUB : Quotation for Modification in Admin's STP 5KLD (PWTS-AM).

Dear Sir,

Thank for your query regarding the Modification in STP (STP Tank), At a time of my Physical Visit at your Plant, Pls find the Quote & Hope the same will be in line of your expectation.

Sr. No	Description	QTY	RATE	AMOUNT
1.	Repair & Maintenance	01		96740.00
2.	Man Days Sintex Expert	02	7500.00	15000.00
	Total			111740.00
	GST @ 18%			20113.00
	Net payable Amount			<u>131853.00</u>

Rs. One Lac thirty one thousand eight hundred fifty three only...

Tank Modification Work Breakup:-

BBELL Industry LLP- Dahej		
	Admin- 5KL PWTS-AM	Qty
1	Blowers 40LPM	2
2	Dosing Pump	1
3	Sodium Hypo	220
4	HD Tank 100 Ltr	1
5	Bact Culture	3KG
6	Nutri Sarv	1KG
7	Pipeline from Blower to STP	40FT
8	Tank Cleaning	1
9	Single Phase Starter for Blower & Dosing System	1



Scope of Work (Customer):-

1. Arrange to Inlet Diversion During the Work in Admin's STP Tank (Approx. 2 Days) will be in Customer scope.
2. All Civil Work will be in Customer Scope like Digging pits, New Civil storage tank etc...
3. Desludging of the Tank with Tankers will be in Customer Scope, If required to clean by Hand that will be arrange by the Sintex.
4. Midea from inside of the tank should be unload from the tank and Cleaned it with fresh water.
5. Single Phase Electric Line Connection lying at Installation Point where both Blower to be install will be in Customer scope.
6. Exhaust Fan, LED Light connection (Inside of the Tank) and waste Cotton Cloths will be in Customer Scope.

Scope of Work (Sintex):-

1. Aeration Pipe line will be Connect from Blower to STP Tank (Inside by the Sintex).
2. Tank Cleaning after Desludging work will be in Sintex Scope.
3. Dosing Pump installation and Pipe for Dosing supply will be install by the Sintex.
4. All Electrical connection from the Main line to Blower & Dosing Pump by the Sintex Only.
5. Defuser will be made by the Sintex for Proper Aeration Supply inside of the Tank.
6. Partition wall inside of the Tank will be Cut by Sintex for Pull the Mideas.
7. After Repairing & Modification work additional Bacterial Culture will be dropped by the Sintex in aeration Chamber.

Terms And Condition:

- 1) **Payment : 100% advance against the Performa Invoice by Cheque or D.D. in favor of Sintex BAPL Ltd – payable at Kalol (North Gujarat).**
- 2) **Transportation cost will be extra as applicable.**

Note: Sintex will not be responsible for any collateral losses occur due to Sintex product failure for any reason.

You are requested to approve the quotation along with Advance payment to enable us to arrange the materials and manpower at site.

Thanks and Regards,
For Sintex BAPL Ltd.