

Toorant Communications

G-4, Hexzone Arcade, Valiya Road, Nr. Jayaben Modi Hospital, Ankleshwar - 393002

Contact No : 9638480441 Email : toorant.c@gmail.com

GST No : 24ASJPJ0259R1ZA

Project BBEL/0522/001

Date 13.12.2022

Validity 15 Days only

Sr. No.	Product Description	Make	Locations	Qty	Unit	Supply Rate	Supply Amount	Labour Rate	Labour Amount
1	2 MP IP Camera - 20 MTR IR Range 1/2.8" Progressive Scan CMOS, 2 megapixel resolution, Digital WDR, 3D DNR, 30 meters IR range, 12V DC±10%, ICR, *power supply no included, PoE Camera, H.265+ Plastic, 2MP, Built In microphone, Memory Card Slot up to 256 GB Memory card needs to purchase saperate if required	Hikvision	Plant Area	26	Nos	4500	117000	800	20800
2	2 MP IP Camera - 50 MTR IR,1/3" Progressive CMOS, ICR, 2560x1440:20fps(P)/(N), 2304x1296:25fps(P)/30fps(N), H.265+/H.265/H.264+&H.264, 3D DNR, BLC, IR range: up to 50m, DC12V & PoE,Support mobile monitoring via Hik-Connect *power supply no included	Hikvision	Utility Area	12	Nos	6250	75000	800	9600
3	PTZ Camera 2MP, 1/2.8" CMOS, 3D DNR, ICR, Color: 0.02lux/F1.5, B/W:0.02lux/F1.5, Optical Zoom:25x, Focus:4.7-94.0mm, Digital Zoom:16X, 1920x1080:30fps, Pan range:360° endless; Tilt range: - 15°~90°(Auto Flip), Pan Speed: 0.1° -400°/s, Tilt Speed: 0.1° - 200°/s, 200m IR Distance, H.265+	Hikvision	Gate Area Plant Top Side	2	Nos	60000	120000	3000	6000

Toorant Communications

G-4, Hexzone Arcade, Valiya Road, Nr. Jayaben Modi Hospital, Ankleshwar - 393002

Contact No : 9638480441 Email : toorant.c@gmail.com

GST No : 24ASJPJ0259R1ZA

Project BBEL/0522/001

Date 13.12.2022

Validity 15 Days only

Sr. No.	Product Description	Make	Locations	Qty	Unit	Supply Rate	Supply Amount	Labour Rate	Labour Amount
4	NVR - 32 CH, 4 SATA, 256 MBPS Security Standard Upgraded, Mobile Push / Email generation	Hikvision	Server Room	2	Nos	30000	60000	5000	10000
5	L2 Managable POE Switch (8+2) - 10/1000 + 10/1000	TP Link	Cable Distribution area	5	Nos	13500	67500	500	2500
6	Omada controller	TP Link	Server	1	Nos	6000	6000	500	500
7	Hard Disk - 4 TB (3+3) in both NVR	Seagate / WD	Server	6	Nos	9500	57000	0	0
8	4 U Rack - Powder Coated	Generic	Office	5	Nos	3000	15000	150	750
9	General Accessories, Cable Tie, Armoured cable bounding wire, nail, RJ45 Connector	Generic	across the site	1	Loose	2000	2000	0	0
10	Fiber Media Connecotor	Syrotech	Distribution area	4	Nos	5000	20000	500	2000
11	Junction Box = Nos of camera	Generic	across the site	40	Nos	100	4000	50	2000
12	Fiber Cable Splicing work			1	Job			2000	2000
	At Actual Charges for Cable								
13	Networking Cable CAT6/Fiber	D Link / DIGISOL	at actual	3050	MTR	35	106750	15	45750
14	PVC Pipe, 25 mm Dia with accessories, White Vergin plast - 10 Feet Long		at actual	200	Nos	150	30000	10	2000
			Total				680250		103900
			GST @ 18%				122445		18702
			Grand Total				802695		122602
			Project Cost				925297		

Terms & Condition

- 1 Electrical connection will be provided by you

Quotaion / Proforma Invoice

Toorant Communications

G-4, Hexzone Arcade, Valiya Road, Nr. Jayaben Modi Hospital, Ankleshwar - 393002

Contact No : 9638480441 Email : toorant.c@gmail.com

GST No : 24ASJPJ0259R1ZA

Project BBEL/0522/001

Date 13.12.2022

Validity 15 Days only

Sr. No.	Product Description	Make	Locations	Qty	Unit	Supply Rate	Supply Amount	Labour Rate	Labour Amount
---------	---------------------	------	-----------	-----	------	-------------	---------------	-------------	---------------

2 you needs to assisst for CLASS 1 Work permit for hazardous area, if required

3 Pipe will be used if the cable tray route is not avaiable, this will helps for proper cable dressing

4 All material is EX Stock

For, Toorant Communications

Authorized Signature